

Government of the People's Republic of Bangladesh
Office of the Refugee Relief and Repatriation Commissioner
Cox's Bazar
www.rrrc.gov.bd

No: 51.04.2200.005.00.032.24- 3333

Date: 15 September 2025

Sub: **Approval of Shelter Models under GoB-Approved TSS Application**

Ref: ISCG's letter no.-(1) ISCG/2025/46, date: 17 August 2025
(2) ISCG/2025/40, date: 17 July 2025

In reference to the above-mentioned subject and letter, the office of the RRRC acknowledges receipt of your letter dated 17 August 2025 regarding the request for approval of four Temporary Safer Shelter (TSS) models in line with the Government of Bangladesh-approved TSS application. After careful review and consideration, the RRRC office is pleased to approve for the implementation of the following two TSS models:

Model 3: **Upgraded Mid-Term Shelter (MTS) with TSS Features**

Model 4: **CGI Roofing & Cement-Soaked Geotextile Shelter (CR&CS-GS) – New TSS Model**

2. However, regarding the model 1 (Mud Tally Shelter-MTS) and Model 2 (Waste Revive Resilient Shelter-WRRS), it has been decided to resubmit the drawing, design and BoQ according to the approved guidelines.

Thank you for your continuous support and cooperations.


Muhammad Talut
(Deputy Secretary)
Mobile: 01847-424197
E-mail: contact@rrrc.gov.bd

Mr. David Bugden
Principal Coordinator
Inter Sector Coordination Group (ISCG)
Cox's Bazar

Copy for kind information:

1. **Additional Refugee Relief and Repatriation Commissioner**, this office
2. **Camp-in-Charge (all)**, Ukhiya/Teknaf, Cox's Bazar.
3. **PS to RRRC** (For kind attention of RRRC).
4. Office Copy.

TSS (Temporary Safer Shelter) **CGI Roofing with Cement Soaked Geo Textile Shelter**

General Notes

Shelter size-10'x15'(150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCCM SECTOR

SCCCM Sector Standards - Bangladesh

Rohingya Refugee Response **SECTOR**
 Bangladesh Cox's Bazar, Bangladesh

Coordination Hub, Kabita Sononi, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title:TSS(Temporary Safer Shelter)
CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No:

Scale:

Sheet No: Top Sheet

Date: June, 2025.

Sketch & Planning by:
 (Shelter taskforce Team)

Drawn by:
 (Meer Md.Ferdous Islam, Syed Naved Zaman & Umi Das)

Design & Checked by:
 () & Shelter taskforce Team

Technical Support & Validated by:
 SCCCM Sector-ISCG and PPPIC



BAVNS WATERLAND PLANT TRUSTS
 FOR NEXT GENERATION

LEGEND:

 Woven Bamboo Mat wall	 RCC Post	 Cement Soaked Geo Textile
 Metal Frame	 CGI Sheet	 Plain Sheet

0 1m 2m

(Signature)
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

(Signature)
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar



General Notes

Shelter size: 10'x15' (150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCCM SECTOR
 SCCCM Sector Standards - Bangladesh
 Rohingya Refugee Response
 SHELTER & CCCM SECTOR
 Cox's Bazar, Bangladesh
 Coordination Hub, Kabila Soroni, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title: TSS (Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No:

Scale: 1:1

Sheet No: 3D View

Date: June, 2025.

Sketch & Planning by:
 [Shelter taskforce Team]

Drawn by:
 [Meer Md Fardous Islam, Syed Naved Zaman & Umi Das]

Design & Checked by:
 [Shelter taskforce Team]

Technical Support & Validated by:
 SCCCM Sector-4SCG and RRRC




LEGEND:

Woven Bamboo Mat wall	RCC Post	Cement Soaked Geo Textile
Metal Frame	CGI Sheet	Plain Sheet

0 1m 2m

[Signature]
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

[Signature]
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar



SHELTER PLAN

General Notes

Shelter size: 10'x15' (150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCCM SECTOR
 SCCCM Sector Standards - Bangladesh
 Rohingya Refugee Response
 Bangladesh
 SHELLER & CCCM SECTOR
 Cox's Bazar, Bangladesh
 Coordination Hub, Kabita Sonari, Motel Road,
 Cox's Bazar-4700, Bangladesh

Project Title: TSS (Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 01

Scale: 1:1

Sheet No: 01

Date: June, 2025.

Sketch & Planning by:
 (Shelter taskforce Team)

Drawn by:
 (Meer Md. Ferdous Islam, Syed Naved Zaman & Umi Des)

Design & Checked by:

Shelter taskforce Team

Technical Support & Validated by:
 SCCCM Sector HSG and PRRC




LEGEND:

- | | | |
|--|--|--|
| | | |
| | | |



Ismail
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Imdad Talut
 Deputy Secretary
 Cox's Bazar



PLINTH BEAM LAYOUT PLAN

General Notes

Shelter size: 10'x15' (150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCCMM SECTOR

SCCCM Sector Standards - Bangladesh

Rohingya Refugee Response
 SHELTER & CCCM SECTOR
 Cox's Bazar, Bangladesh

Coordination Hub, Kabita Sononi, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title: TSS (Temporary Safer Shelter)
CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 02

Scale: 1:1

Sheet No: 02

Date: June, 2025.

Sketch & Planning by:
 [Shelter taskforce Team]

Drawn by:
 [Meer Md.Ferdous Islam, Syed Nasir Zaman & Umri Das]

Design & Checked by:
 [Shelter taskforce Team]

Technical Support & Validated by:
 SCCCMM Sector-ISC and RRRC




LEGEND:

Woven Bamboo Mat wall
 Metal Frame
 RCC Post
 CGI Sheet
 Cement Soaked Geo Textile
 Plain Sheet




Md. Ismail Hossain
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Muhammad Talut
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar




Md. Ismail Hossain
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Muhammad Talut
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar




Ismail
Md. Ismail Hossain
Care & Maintenance Officer
RRRC Office, Cox's Bazar

Talut
Muhammad Talut
Deputy Secretary
RRRC Office, Cox's Bazar



Md. Ismail Hossain
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Muhammad Talut
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar



TRUSS DETAILS

General Notes

Shelter size-10'x15'(150 sqft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCC Sector
 SCCC Sector Standards - Bangladesh
 Rohingya Refugee Response
 Shelter & CCCM Sector
 Cox's Bazar, Bangladesh
 Coordination Hub, Kabita Sononi, Motel Road,
 Cox's Bazar-4700, Bangladesh

Project Title: TSS(Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 06

Scale: 1:1

Sheet No: 06

Date: June, 2025.

Sketch & Planning by:
 (Shelter taskforce Team)

Drawn by:
 (Meer Md.Ferdous Islam, Syed Naved Zaman & Umit Das)

Design & Checked by:
 (Shelter taskforce Team)

Technical Support & Validated by:
 SCCC Sector-ISCG and RRRC




LEGEND:

Woven Bamboo Mat wall
 Metal Frame
 RCC Post
 CGI Sheet
 Cement Soaked Geo Textile
 Plain Sheet



Signature
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Signature
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar



ROOF SECTION (A-A) DETAILS

General Notes

Shelter size-10'x15'(150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCC Sector
 SCCC Sector Standards - Bangladesh
 Rohingya Refugee Response
 Shelter & CCCM Sector
 Cox's Bazar, Bangladesh
 Coordination Hub, Kabita Soroni, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title: TSS (Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 07

Scale: 1:1

Sheet No: 07

Date: June, 2025.

Sketch & Planning by:
 (Shelter taskforce Team)

Drawn by:
 (Meer Md. Faridul Islam, Syed Naved Zaman & Umi Des)

Design & Checked by:
 S Shelter taskforce Team

Technical Support & Validated by:
 SCCC Sector-ISCG and PPRC




LEGEND:




Md. Ismail Hossain
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Muhammad Talui
 Muhammad Talui
 Deputy Secretary
 RRRC Office, Cox's Bazar




Ismail
Md. Ismail Hossain
Care & Maintenance Officer
RRRC Office, Cox's Bazar


Muhammad Talut
Muhammad Talut
Deputy Secretary
RRRC Office, Cox's Bazar



MAIN DOOR DETAILS (METAL)



WINDOW DETAILS



WINDOW GRILL DETAILS

General Notes

Shelter size: 10'x15' (150 sq ft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCC Sector
 SCCC Sector Standards - Bangladesh
 Rohingya Refugee Response
 Shelter & CCCM Sector
 Coordination Hub, Kabila Soroni, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title: TSS (Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 09

Scale: 1:1

Sheet No: 09

Date: June, 2025.

Sketch & Planning by:
 [Shelter taskforce Team]

Drawn by:
 [Meer Md.Ferdous Islam, Syed Naved Zaman & Umi Des]

Design & Checked by:
 [Shelter taskforce Team]

Technical Support & Validated by:
 SCCC Sector-SCG and RRRC




LEGEND:




[Signature]
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

[Signature]
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar



MATERIAL REQUIREMENTS
 cement: portland cement (PCC CEMII), fresh (≤2 months old).
 sand: sand (FM-1.2-1.5mm), clean, sharp-edged, and silt-free (max 3% silt content).
 Aggregate: Coarse aggregate (size-20mm down well graded), clean, sharp-edged, and dust-free
 water: clean, pH 6-8 (no salinity/organic matter).
 Reinforcement: 6mm-10mm mild steel deformed bars (grade 60).
 Form work: form work -Steel/wood shutter
MORTAR MIX PROPORTION
 ratio: 1 part cement : 1.5 parts sand : 3 parts aggregate (by volume).
 consistency: concrete slump 40-60mm
 Curing: submerged by water/covered by wet hessian cloths/ water spray 5x/day for minimum 14 days; avoid direct sunlight
TECHNICAL PERFORMANCE
 compressive strength: ≥20 mpa at 28 days.
QUALITY CONTROL CHECKS
 before casting: ensure clear cover & verify bar overlap (min. 400mm), no rust on steel.
 during casting: ensure mix proportion, shutter work, no voids; use needle vibrator if needed.
 post-casting: ensure curing



General Notes

Shelter size-10'x15'(150 sft)
Flooring: Sand & Cement
Plinth Beam: Cement & sand mortar
Wall: Bamboo mat with cement soaked Geo-textile wall
Structure: Metal frame, Precast RCC post footing foundation footing foundation
Roofing: CGI sheet with cement soaked geo textile insulation

ISCG SCCC Sector
 SCCC Sector Standards - Bangladesh
 Rohingya Refugee Response
 Shelter & CCCM Sector
 Cox's Bazar, Bangladesh
 Coordination Hub, Kabita Soroni, Motel Road, Cox's Bazar-4700, Bangladesh

Project Title: TSS(Temporary Safer Shelter)
 CGI Roofing with Cement Soaked Geo Textile Shelter

Project No: 01

Drawing No: 10

Scale: 1:1

Sheet No: 10

Date: June, 2025.

Sketch & Planning by:
 [Shelter taskforce Team]

Drawn by:
 [Meer Md.Ferdous Islam, Syed Naved Zaman & Umi Das]

Design & Checked by:
 [Shelter taskforce Team]
Technical Support & Validated by:
 SCCC Sector-4ISG and PRRC



LEGEND:

Woven Bamboo Mat wall	RCC Post	Cement Soaked Geo Textile
Metal Frame	CGI Sheet	Plain Sheet



Signature
 Md. Ismail Hossain
 Care & Maintenance Officer
 RRRC Office, Cox's Bazar

Signature
 Muhammad Talut
 Deputy Secretary
 RRRC Office, Cox's Bazar

COST ESTIMATION FOR TEMPORARY SAFER SHELTER- CGI ROOFING & CEMENT SOAKED GEOTEXTILE

Rohingya
Refugee
Response
Bangladesh

SHELTER & CCCM
SECTOR
Cox's Bazar, Bangladesh



Flooring	Sand and cement plaster with NCF finishing
Footing	RCC Precast Post with T Shape
Structure (post) +	RCC Precast Post
Wall Plate + Rafter + Beam + Purlin	MS Angle
Walling	Bamboo Mat with Geo textile cement Sheet
Roofing	CGI Sheet with geo textile cement sheet and MS angle frame

BoQ - CGI ROOFING & CEMENT SOAKED GEOTEXTILE 150 Sq-ft

SL No.	Items	Size/Specification	Location /Item	Unit	Quantity
Substructure:					
1	Earth Excavation	Earthwork in excavation of foundation trenches, including layout, by excavating earth to the lines, grades and elevation as shown in the drawing providing center lines, local bench mark pillars, fixing bamboo spikes and marking layout with chalk powder filling baskets, carrying and disposing of all excavated materials at a safe distance designated by the E-I-C in all types of soils except rocky, gravelly, slushy or organic soil, leveling, ramming, dressing and preparing the base, etc. all complete for an initial excavation depth of 2m and an initial lead not exceeding 20m, including arranging all necessary tools and equipment at work site, etc. complete as per direction of the E-I-C.	Footing	cft	46.89
2	Precast RCC Post	Supplying, fitting & fixing of Precast Reinforced Cement Concrete Post size-5" x 5" x 10'- 6" (T-Shape) - including 5nos clamp (cement PCC: coarse sand FM-1.2:Aggregate first class brick chips 20mm down graded) LAA value not exceeding 30, including shuttering, mixing by concrete mixer machine, casting, laying compacting, curing for the requisite period etc. all complete as per design, drawing, specification and direction of the E-I- C.Including the cost of reinforcement. Strength of concrete should not be less than 20 MPa (suggested mix proportion 1:1.5:3).	Footing with column	Pcs	9
3	Sand Filling	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by theEngineer-in- charge..	Flooring	cft	124.95
4	Plinth Beam	Supplying, making of plinth beam -8" x 10" x L -(cement PCC: coarse sand FM-1.2: including shuttering by bamboo slice with polythene sheet, mixing, laying compacting, curing for the requisite period etc. all complete as per design, drawing, specification and direction of the E-I-C. (suggested Cement :sand mix proportion 1:8).	Plinth Beam	cft	27.39
5	Plaster work 25mm with NCF finishing	Minimum 25mm thick cement plaster (1:4) & neat cement finishing with Portland Composite cement (CEM II/AM, 42.5N) and best quality sand (minimum FM1.2) to dado, Plinth Floor or any where directed with neat cement finishing in/c washing of sand, racking out joint and picking up cement mortar i/c finishing the edges and corners and curing for the requisite period etc. all complete as per direction of the E-I-C.	Flooring	sft	150
Superstructure:					
6	Geo Textile with cement mix sheet	Supplying, fitting & fixing of Geo Textile with cement mix sheet (cement PCC, 300gsm geo textile) including mixing with water & cement, water:cement ratio: 1:1.5, soaking period 25 miniutes, laying/fixixg with botom ot roof CGI sheet and bamboo mat, curing for the requisite period etc. all complete as per design, drawing, specification and direction of the E-I-C.	Walling & Roofing	sft	1152
7	Woven Bamboo Mat	Supplying, fitting & fixing of Single Layer woven muli bamboo mat including Labor all complete as per design, drawing, speccification and direction of the E-I-C.	Walling	sft	364
8	Tarpaulin	Supply,Fitting & fixing of Tarpaulin Size: Width 4 m ± 1% net width,Length 6m minimum net length, Weight: 200g/m² ± 20g under ISO 3801 (equivalent to 180g/m² minimum to 210g/m² maximum. Colour: White sun reflective on both sides of the sheet. Grey coating on the outside of the bands. Inner black fibres to ensure opacity.Need to follow Red cross approved specification.	Walling	pcs	2
9	CGI Color Sheet	Supplying, fitting and fixing of CGI Color Sheet 0.32mm thick, corrugated galvanized colour iron sheet (Bangladesh made)having minimum weight 50-53 kg per bundle (2'-6" width 70 – 72 rft long) roofing fitted and fixed on metal purlins with Approximately 13 roofing screws with sealing washer, rubber/m2, Nails, limpet washers, bitumen washers and putty etc. all complete as per design, drawing, specification and direction of the E-I-C.	Roofing	sft	252
10	Ridge	CGI Color sheet: 7' long, 0.32mm thick	Roofing	pcs	4
		Supplying, fitting and fixing of ridge 300mm width 0.32mm thick corrugated galvanized colour iron sheet ridging with 300mm lap on either side fitted and fixed with galvanized bolts and nuts etc. all complete as per design, drawing, speccification and direction of the E-I-C.			
		Ridge: 6' Long. 300mm width. 0.32mm thick			

SL No.	Items	Size/Specification	Location /Item	Unit	Quantity
11	MS Angle	Supplying, fitting & fixing of MS Angle with nut bolt connection joint including fabrication and conforming to ASTM A36, with a minimum yield strength of 250 MPa application of red/grey-oxide primer etc. all complete as per drawing, specification and direction of Engineer-in-charge.	wallplate, Rafter and wall & roof purlin	kg	575
		MS Angle, L 50mmx50mmx5mm			
		MS Angle, L 40mmx40mmx3mm			
12	MS Flat Bar	Supplying, fitting & fixing of MS Flatbar including fabrication and conforming to ASTM A36, with a minimum yield strength of 250 MPa application of red/grey-oxide primer etc. all complete as per drawing, specification and direction of Engineer-in-charge.	Walling Garenja	kg	35
		MS Flatbar, 25mmx3mm			
13	Nut ,Bolt & Washer	Supplying, fitting & fixing of 25mm dia Nut ,50mm long 8mm dia Bolt & 25mm dia Washer etc. all complete as per Design, Specification & direction of the E-I-C.	Walling & Roofing	set	150
14	GI wire	Supplying, fitting & fixing of GI wire #18 dia 1.00mm thickness	for fixing bamboo	Kg	8
15	Lock	Small durable padlock with 2 keys 40mm width, 30mm height & thickness 13mm	For door locking	Set	1
16	Door	Door(Double Shutter-Size: 3'-4" x 7'): Supplying, fitting and fixing door as per design angle frame, plain sheet shutter with fixing 6 nos. of 100mm size iron hinges and 200mm long lock with the vertical members of the frame for double leaf shutter, painting all iron & shutter faces both side in 2 coats over a coat of priming with enamel paint of approved colour and quality in/c cutting, sizing, welding for all floors, etc. all complete as per Design, Drawing, Specification & direction of the E-I-C.	Door	Nos	1
17	Window	Window (Double Part, Size:3'-4"x4'-6"): Supplying, fitting and fixing of window angle frame, plain sheet shutter with fixing 100x50mm size 8 nos. of ss hinge, 150mm long ss lock 2 nos, angle frame- Chowkat, Outer frame & inner frame size as per design, with the vertical members of the frame for double leaf 18 gauge MS Plain shutter, including window MS grill, Enamel painting all metal & shutter faces both side in 2 coats of approved colour and quality in/c cutting, sizing, including necessary fixing materials for all floors, etc. all complete as per Design, Specification & direction of the E-I-C.	Window	Nos	3
18	Nail	1" length, SS type	joints	kg	1

Methodologies & Quality Assurance

Step	Description of work	Methodology	Quality Assurance method	Remarks
1	Layout	<ol style="list-style-type: none"> 1. The site should be cleared from all debris. 2. Layout should be provided following the layout plan and site plan. 3. bamboo sticks and ropes may be used for demarcation 	<ol style="list-style-type: none"> 1. The layout should be cross-checked to ensure the proper alignment. 2. No layout will be provided in high-risk area. 	
2	Column installation	<ol style="list-style-type: none"> 1. Column should be constructed as per the specification and properly cured for atleast 14 days which will be delivered by the vendor. 2. The earth excavation to be done as per the layout plan to install the columns properly. 	<ol style="list-style-type: none"> 1. The columns must be checked while casting & receiving. 2. During installation the column should be straight at 90 degree. 3. face of the column should be as per the plan. 	
3	Plinth improvement	<ol style="list-style-type: none"> 1. The plinth is to be dugged along the periphery of the shelter to get a clear 10"X8" size 2. Multi bamboo (from shelter waste) made formwork to be laid with single layer polythene inside 3. A mix of cement and sand of ratio (1:6) is poured in the formwork and compacted properly. 	<ol style="list-style-type: none"> 1. The earth cutting should be well aligned. 2. Ramming should be done properly before laying formwork. 3. compaction to be done properly so that no void remains. 4. Proper curing has to be done. 	
4	Skeletal element installation	<ol style="list-style-type: none"> 1. All the angles should be cut as per specification mentioned in the design. 2. The joints are to be done by point welding. 3. All the metal components should be painted with lead-oxide to avoid corrosion. 	<ol style="list-style-type: none"> 1. Safety gears is a must for all the labors during the whole process. 2. The welding should be done properly at all the joints. 	
5	Wall installation	<ol style="list-style-type: none"> 1. The woven bamboo mat is to be prepared as per the dimension mentioned in the drawings. 2. Provision for doors and windows should be maintained as per the drawing details. 3. The bamboo mat panels can be put in place and tied with the columns by using GI wires. 4. The geotextile sheet needs to be cut in size depending on the size of each wall. 5. Tarpaulin are to be put on the outer part of the mat and tied properly. 6. The geotextile sheets are to be soaked in cement slurry comprising of Cement and water at 1.5:1 ratio for 25 mins. 7. The soaked geotextile sheet are to be put on mats on both sides and tied with GI wire. 	<ol style="list-style-type: none"> 1. While cutting the geotextile it needs to be cutted 4~5" more than the actual panel size to avoid reducing area due to shrinkage. 2. The soaking should be carried out for minimum 25 minutes. 3. The geotextile sheets should be properly soaked ensuring no dry space. 4. while wrapping the bamboo mat the tying with GI wire to be ensured properly to reduce the gap between mat and geotextile sheet after drying. 5. Proper curing is a continuous process upto end of construction time, which is 14 days but atleast 7 days curing should be done. 6. The labour should use safety gears during installation. 	

Step	Description of work	Methodology	Quality Assurance method	Remarks
6	Roof installation	<ol style="list-style-type: none"> 1. A layer of cement soaked geotextile to be put over the rafters and tied very tightly to avoid sagging. 2. The geotextile sheets are to be soaked in cement slurry comprising of Cement and water at 1.5:1 ratio for 25 mins. 3. After drying the geotextile sheet for 2~3 days the CGI sheets are to be placed properly above the cement-soaked geotextile sheet and fitted properly with the angles using screws. 	<ol style="list-style-type: none"> 1. While cutting the geotextile it needs to be cutted 4~5" more than the actual panel size to avoid reducing area due to shrinkage. 2. The soaking should be carried out for minimum 25 minutes. 3. The geotextile sheets should be properly soaked ensuring no dry space. 4. All components should be tied properly using GI wire. 5. The screws should be placed tightly with caps to avoid any leakage. 6. Proper curing is a continuous process upto end of construction time, which is 14 days but atleast 7 days curing should be done. 7. The labour should use safety gears during installation. 	
7	Floor making	<ol style="list-style-type: none"> 1. The earth should be properly compacted by ramming. 2. A layer of polythene should be laid on floor. 3. A layer of cement sand mixture of ratio 1:4 would be laid on floor at a thickness of 1" and a layer of cement slurry to be put on as neat cement finishing layer. 	<ol style="list-style-type: none"> 1. The compaction should be done properly or else crack may appear after casting. 2. Proper curing has to be done. 	